

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas, 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 11 TWP. 35 RGE. 13w E/W
Location as in quarters or footage from lines:
NE NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Okmar Oil Company
Lease Name Achenback "A" #4 Well No. _____
Office Address Box 723, Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 7/11/83
Plugging completed 7/19/83
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Benny Beck
Producing formation _____ Depth to top _____ bottom T.D. 4880'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	247'	none
				4 1/2"	4873'	3427'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4750' & 4 sacks cement. Shot pipe at 3800',
3605', & 3410'. Pulled total of 107 joints of pipe. Plugged well with
3 hulls, 10 gel, 50 cement, 1 hull, 10 gel, plug, & 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso

(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347, Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 83



[Signature]
Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: _____

JUL 28 1983

CONTRACTOR'S WELL LOG

OPERATOR: Okmar Oil Company
 CONTRACTOR: Union Drilling Co., Inc.
 WELL NAME: Achenbach "A" #4
 LOCATION: NE NE NE Section 11-35S-13W
 Barber County, Kansas
 COMMENCED: August 17, 1976
 COMPLETED: August 28, 1976

0	250	Redbed and shale	
250	2055	Shale	8-5/8" casing set at 247' with
2055	2272	Lime and shale	200 sacks
2272	2706	Shale and shells	
2706	2884	Lime and shale	
2884	3191	Shale and lime	
3191	4299	Lime and shale	
4299	4537	Lime	
4537	4625	Lime and shale	
4625	4742	Lime	
4742	4880	Lime and shale	
4880		T. D.	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 04 1983
 WICHITA, KANSAS

We certify that the above and foregoing is a true and correct copy of the log on the Achenbach "A" #4, NE NE NE Section 11-35S-13W, Barber County, Kansas.

UNION DRILLING CO., INC.

R. D. Messinger
 R. D. Messinger

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public in and for the aforesaid county and state as of this 30th day of August, 1976.

Donna F. Brown
 Donna F. Brown, Notary Public

My commission expires:
 July 29, 1978

