

15-051-00392-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
213 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County, Sec. 1 Twp. 13 Rge. (E) 17(W)

Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Weigel Well No. 1
Office Address 414 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/11 19 59
Application for plugging filed 3/11 19 59
Application for plugging approved 3/11 19 59
Plugging commenced 3/11 19 59
Plugging completed 3/11 19 59
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	489	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy mud
Plug @ 550' 20 sacks cement
Plug @ 150' 15 sacks cement
Plug @ 40' 10 sacks cement

RECEIVED
MAR 21 1959
CONSERVATION DIVISION
Wichita, Kansas
63-20-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 414 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. _____
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson
414 Union Center
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 59

Esther Laman
Notary Public.

My commission expires Jan. 19, 1961

PLUGGING
FILED MAR 13 1959
BOOK PAGE 23 LINE 31

DRILLERS LOG
 TOMLINSON-KATHOL, INC.
 # 1 WEIGEL
 SE NW NW, SEC. 1-13S-17W
 ELLIS COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced - 3/2/59
 Completed - 3/11/59
 Elevation 2054 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	155	Clay	
155	179	Shale - Clay	
179	320	Shale	
320	680	Clay & Shale	489' 8-5/8" w/125 sks cement
680	725	Shale & hard sand streaks	
725	863	Shale & loose sand streaks	
863	878	Sand	
878	976	Red Bed	
976	1212	Red Bed & Shale	
1212	1265	Anhydrite	
1265	1830	Shale & Shells	
1830	2050	Shale & Lime	
2050	2150	Lime	
2150	2315	Lime - Shale	
2315	2420	Lime & Shale	
2420	2505	Shale	
2505	2620	Shale & Lime	
2620	2695	Lime & Shale	
2695	2845	Shale	
2845	3021	Lime & Shale	
3021	3123	Shale	
3123	3234	Lime	
3234	3320	Shale & Lime	
3320	3434	Lime & Shale	
3434	3485	Lime	Heebner 3275
3485	3539	Lime & Shale	Toronto 3294
3539	3590	Lime	Lansing 3323
3590	3657	Lime & Shale	Base K.C. 3553
3657	3657	Conglomerate	Conglomerate 3612
3657	3685	Arbuckle	Arbuckle 3657
3685		Rotary Total Depth	RTD 3685

RECEIVED
 STATE OF KANSAS
 03-20-1959
 MAR 20 1959
 CONSERVATION DEPARTMENT
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
 Warren E. Tomlinson

State of Kansas)
)
 County of Sedgwick)

Subscribed and sworn to before me this 16th day of March, 1959.

Esther Lamson
 Notary Public

My commission expires 1/19/61

PLUGGING
 FILE SEC. 1 T. 13 R. 17W
 BOOK PAGE 23 LINE 31