


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ellis County, Sec. 1 Twp. 13S Rge. 17 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
App. E $\frac{1}{2}$  SE SE, 350FEL-540FSL of Sec. \_\_\_\_\_  
Lease Owner L&B Leasing  
Lease Name Liker Well No. 1  
Office Address 510 E 15th Ellis, Kansas 67637  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed June 25 1981  
Application for plugging filed June 25 1981  
Application for plugging approved June 25 1981  
Plugging commenced June 25 1981  
Plugging completed June 25 1981  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3610'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	209'	8 5/8"	209'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

1st Plug set at 660' with 65 sacks common cement 50-50 poz 4% Gel 3% Cal cl  
2nd Plug set at 240' with 30 sacks common cement 50-50 poz 4% Gel 3% Cal cl  
3rd. Plug set at 40' with 10 sacks common cement 50-50 poz 4% Gel 3% Cal cl  
5 sacks in rathole  
Heavy drilling mud between each plug

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Graham, ss.  
Jerry M. Helberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.


(Signature)

Jerry M. Helberg  
Box 32 Morland, Kansas 67650  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 81

Janice Robinson  
Notary Public.

My commission expires 12-4-83



RECEIVED  
STATE CORPORATION COMMISSION  
07-06-1981  
JUL - 6 1981  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

LIKER #1

CASING RECORD:

8 5/8" set at 209'

TOTAL DEPTH:

3610'

OPERATOR: L&B Leasing

CONTRACTOR: Helberg Oil Company

COMMENCED: June 16, 1981

COMPLETED: June 26, 1981

DESCRIPTION:

Sec. 1, Twp. 13S, Rge. 17W  
App E½ SE SE, 350FEL-540FSL of Sec.

FORMATION	TO	FROM	REMARKS
Sand and Shale	0	229	
Sand and Shale	229	510	
Sand and Shale	510	1075	
Sand and Shale	1075	1172	
Anhydrite	1172	1210	
Sand and Shale	1210	1325	
Shale	1325	1427	
Shale	1427	1555	
Shale	1555	1901	
Shale	1901	2112	
Shale	2112	2245	
Shale	2245	2395	
Shale and Lime	2395	2536	
Shale and Lime	2536	2660	
Lime and Shale	2660	2847	
Lime and Shale	2847	2986	
Lime and Shale	2986	3072	
Lime	3072	3145	
Lime and Shale	3145	3215	
Lime and Shale	3215	3260	
Lime	3260	3301	
Lime and Shale	3301	3371	
Lime	3371	3377	
Lime	3377	3393	
Lime and Shale	3393	3466	
Lime	3466	3516	
Lime	3516	3580	
Lime	3580	3610	
T.D.	3610		

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1981  
07-06-1981  
CONSERVATION DIVISION  
Wichita, Kansas

D&A

I certify that the above is a true and correct copy of the log to the best of my knowledge.

Helberg Oil Company

*Handwritten signature of Jerry M. Helberg*  
\_\_\_\_\_  
Jerry M. Helberg

Subscribed and sworn to before me this 30 day of June, 1981.

*Handwritten signature of Notary Public*  
\_\_\_\_\_  
Notary Public

My commission expires 12-31-82

