

WELL PLUGGING RECORD

OR

Strike out upper line when reporting plugging off formations.

FORMATION PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Ellis County, Sec. 8 Twp. 13 Rge. 17 (E) 17 (W)
 Location as "NE 1/4 SW 1/4" or footage from lines. 330' from S. Line and 330' from
 Lease Owner. Sibley Oil Company West Line
 Lease Name. E. Staab Well No. 1
 Office Address. Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
 Date well completed. February 15, 1949 19
 Application for plugging filed. February 17, 1949
 Application for plugging approved. February 15, By field Plugger 1949
 Plugging commenced. February 15, 1949
 Plugging completed. February 15, 1949
 Reason for abandonment of well or producing formation. Dry and Abandoned

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes.....

Name of Conservation Agent who supervised plugging of this well.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....3316.....Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with Heavy Mud, set first cement plug at 150', cemented through drill pipe with 15 sacks cement and top plug was set 30' and cemented with 10 sacks cement, plug moved recemented with 5 sacks of cement and filled hole

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Murfin Drilling Company.....
Address.....Union National Bank Bldg.,.....Wichita, Kansas.....

STATE OF Kansas COUNTY OF Sedwick ss

..... (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

SUBSCRIBED AND SWORN to before me this 17th day of February, 1969

My commission expires.

FILE SEC 8 T 13 P 17W
BOOK PAGE 83 LINE 21

02-17-1949

15-051-19346-00-00

Murfin Drilling Co.,
Union National Bank Bldg.
Wichita, Kansas

Sec. 8, T23, R17W
SW c of the S.W. 1/4
County, Ellis
State, Kansas

E Stash No. 1

Total Depth 3616'
Comm. 2-2-49 Comp. 2-15-49

CASING	8 5/8"	15 1/2" cas.	Production D & A
Surface Clay		0 to 65	
Sandy Shale		65 105	
Shale		105 400	
Red Bed		400 575	
Sand		575 625	
Shale & Shells		625 745	
Sand		745 930	
Red Bed & Shells		930 1275	
Lime		1275 1515	
Shale & Shells		1515 1580	
Lime, Shells & Shale		1580 1685	
Pyritic Lime		1685 1720	
Lime & Shale		1720 1845	
Shale & Shells		1845 1975	
Lime		1975 2075	
Lime & Shale		2075 2160	
Lime		2160 2425	
Lime & Shale		2425 2545	
Lime		2545 2680	
Shale		2680 2720	
Lime		2720 2760	
Lime & Shale		2760 2830	
Lime		2830 2842	
Shale & Lime		2842 2945	
Lime		2945 3000	
Lime & Shale		3000 3060	
Lime		3060 3080	
Lime & Shale		3080 3260	
Lime		3260 3275	
Lime & Shale		3275 3398	
Lime		3398 3440	
Lime & Shale		3440 3616	

02-17-1949

PLUGGING
FILE SEC 8 T 13 R 17 W
HOCK PAGE 21