


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-05536-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 11 Twp. 13 Rge. 17 (1/1) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NW/SW/SW
Lease Owner Wilkinson Drilling, Inc.
Lease Name Pete Dreiling Well No. #2
Office Address East 10th, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 3-3 19 59
Plugging completed 3-9 19 59
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3605' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,031'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3605'.
Plugging started 3-3-59. Finished 3-9-59.
Plugged off bottom and sanded to 3340'. Dumped 5 sacks cement and worked pipe. Worked and shot pipe. Shot 5 1/2" casing at 3,031'.
Mixed and circulated 30 sacks mud and 20 sacks cement at 500', and 20 sacks cement at 150'. Bailed out hole to 35'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1959
03-12-1959
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes d/b/a. Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1959

My commission expires November 8, 1960
Betty S. Edman Notary Public.

PLUGGING
FILE SEC. 11 T. 13 R. 17W
BOOK PAGE 12 LINE 45

15-051-05536-00-00

WILKINSON DRILLING INCORPORATED
1121 UNION NATIONAL BUILDING
WICHITA 2, KANSAS

DREILING #2

Company:	WILKINSON DRILLING, INC.	Location:	NW/4 SW/4 SW/4
Contractor:	Company Tools		Section 11-13S-17W
			Ellis County, Kansas
Commenced:	August 17, 1957	Elevation:	2017 DF
Completed:	August 29, 1957	Casing:	SET 10 jts. 8 5/8" casing
Total Depth:	3605'		@ 206.94'

SIGURES INDICATE BOTTOMS OF FORMATIONS

DEPTH	FORMATION
0 - 70	Clay
70 - 200	Shale
200 - 450	Shale, shells and chalk
450 - 690	Red bed, shale and shells
690 - 1185	Shale and shells
1185 - 1215	Anhydrite
1215 - 1280	Shale
1280 - 1900	Shale and shells
1900 - 2110	Shale and lime
2110 - 2280	Lime and shale
2280 - 2950	Shale and lime
2950 - 3065	Lime and shale
3065 - 3264	Lime
3264 - 3350	Lime and shale
3350 - 3545	Lime
3545 - 3605	Arbuckle
3605 -	Total Depth

We hereby certify the above and foregoing to be a true and correct copy of the log on the No. 2 Dreiling located in the NW/4 SW/4 SW/4 of Section 11-13S-17W, Ellis County, Kansas.

WILKINSON DRILLING, INC.

PLUGGING	
FILE SEC. 11 T. 13 R. 17W	
BOOK PAGE 10 LINE 45	

Walter W. Kerschner
REC-6
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this twenty-seventh day of February 8 1959
hundred and fifty-nine.

FEB 28 1959
02-28-1959
CONSERVATION DIVISION
Wichita, Kansas

Carolyn S. Moore

My commission expires January 2, 1961.