


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15-051-00551-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
 Section Plat

County: Ellis Sec. 11 Twp. 13S Rge. 17W (E) _____ (W) _____
 Location as "NE/CNW/SW" or footage from lines NW NW NE
 Lease Owner Sierra Petroleum Co., Inc.
 Lease Name Rome Well No. 1
 Office Address 420 W. Douglas Ave., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) dry
 Date well completed 7/12/57 19
 Application for plugging filed 7/11/57 19
 Application for plugging approved 7/11/57 19
 Plugging commenced 7/12/57 19
 Plugging completed 7/12/57 19
 Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3625 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3625 up to 500'. Set wooden plug, 1/3 sack hulls and 25 sacks cement. Filled with heavy mud from 500' up to 40'. Set plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
 Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
T. R. Sullivan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.R. Sullivan

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 57

My commission expires 1-30-61.

Margie Cooper
 Notary Public.

07-18-1957
 JUL 18 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING	
FILE SEC .11 T. 13 R. 17W	BOOK PAGE 20 LI E 29

15-051-00551-00-00

Sierra Petroleum Co., Inc.

ROME #1

NW NW NE 11-13S-17W
Ellis County, Kansas

Total Depth: 3625

Elev: 2045 KB

Comm: 6/30/57

Comp: 7/12/57

Casing:

8 5/8" @ 210'

Cement:

135 sacks cement

FORMATION	DEPTH
Shale & clay	45
Sand & shale	70
Shale	400
Sand	445
Shale	600
Sand & pyrite	680
Sand	870
Shale	1030
Red bed & shale	1200
Anhydrite	1250
Shale & red bed	1600
Salt & shale	1750
Shale & shells	1800
Shale & lime	2225
Lime	2350
Lime & shale	3065
Lime	3416
Lime & chert	3456
Lime	3567
Arbuckle	3625

Tops:		
Heebner		3258
Toronto		3280
Lans. K. C.		3305
Arbuckle		3562

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 17th day of July, 1957.

[Signature: Annie Cooper]
 Notary Public

My commission expires: 1-30-61.

07-18-1957

PLUGGING
FILE 550 11 T 13 R 17W
BOOK PAGE 28 LINE 29