

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

County, Sec. 11 Twp. 13 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW/SW/NE  
Lease Owner Sierra Petroleum Co. Inc.  
Lease Name Rome Well No. #2  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Yes 19\_\_\_\_  
Application for plugging approved Yes 19\_\_\_\_  
Plugging commenced 5-27 19 58  
Plugging completed 6-5 19 58  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3483' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		2948'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 3483'.  
Plugging started 5-27-58. Finished 6-5-58.  
Plugged off bottom and sanded back to 3330'. Dumped 5 sacks cement.  
Shot 5 1/2" casing at 2948'. Pumped 12 sacks mud. Pulled pipe to 500'  
and pumped 20 sacks cement. Pulled pipe to 200' and pumped 20 sacks  
cement. Finished pulling pipe. Mudded to 35' and capped well with  
10 sacks cement. Well completed.

06-10-1958

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1958

My commission expires November 8, 1960

Petty S. Edman Notary Public.

PLUGGING  
FILE SEC. 11 T. 13 R. 17W  
BOOK PAGE 100 LINE 24

15-051-01183-00-00

Oil Trading Associates - Owner

Sierra Petroleum - Contr.

HOME #2

SW SW NE Sec. 11-125-170  
Ellis County, Kansas

Total Depth 3655'

Elev: 2037 KB

Comm: 4/17/58

Comp: 4/28/58

Casings

8 9/8" @ 216'  
5 1/2" @ 3504

Cement:

with 150 sacks cement  
with 75 sacks cement

FORMATION	DEPTH
Surface clay	49
Sand & shale	70
Shale	125
Shale & shells	465
Shale	720
Sand	840
Shale & red bed	1205
Anhydrite	1239
Shale & shells	1640
Shale & lime	3280
Lime	3560
Congl.	3590
Arbuckle	3655

Tops:		DEPTH
Anhydrite		1205
Haebaer		3257
Toronto		3277
Lansing K. C.		3304
Base K. C.		3522
Conglomerate		3540
Simpson		3560
Arbuckle		3573

STATE OF KANSAS )  
COUNTY OF RUSSELL ) 223

I hereby certify that the above information is true and correct to the best of my knowledge.

A. P. Henderson

Subscribed and sworn to before me this 28th day of April, 1958.

Margie Cooper  
Notary Public

My commission expires: 1-30-61.

RECEIVED  
STATE DEPARTMENT OF CONSERVATION

MAY 14 1958  
05-14-1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 11 T. 12 R. 17W  
BOOK PAGE 100 LINE 24