

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Edgemoor Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,501-00-00

LEASE NAME FRANCIS

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION SW SW SW

SEC. 19 TWP. 13 RGE. 17 ~~XXXX~~ (W)

COUNTY ELLIS

Date Well Completed 9-9-87

Plugging Commenced 9-30-87

Plugging Completed 9-30-87

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH, HAYS KS 67601

PHONE # (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? YES if not, is well log attached? _____

Producing formation NA Depth to top _____ bottom T.D. 3721

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
SURFACE		SURF	204	8 5/8"	207	NONE
PRODUCTION		SURF	3719	4 1/2"	3719	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

PLUGGED W/150 SACKS 65/35 POXMIX 6% GEL 2% ECONOLITE
SANDED BOTTOM OF HOLE WITH 5 SACKS OF SAND AND 4 SACKS CEMENT. SHOT PIPE
ONCE AND RECOVERED 2700' OF PIPE. CEMENTED THRU 8 5/8" 5 SACKS OF HULLS,
150 SX THRIFTY MIX, MAXIMUM PRESSURE 500#'s.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION License No. 5128
Address 207 W 12TH, HAYS KS 67601

STATE OF KANSAS COUNTY OF ELLIS, ss.


R P NIXON

~~XXXXXXXXXX~~ operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) R P Nixon

(Address) 207 W 12TH, HAYS KS 67601



OCT 29 1987
10-29-1987
CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 27 day of OCTOBER, 1987

Lorna M Herrman
Notary Public
Lorna M Herrman

My Commission expires: 6-19-88