


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 19 Twp. 13S Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines 1650' FSL & 2310' FSL or NW NE SW
Lease Owner Clinton Oil Company
Lease Name MADDEN Well No. 2-X
Office Address 6810 West Highway U.S. 54, Wichita 9, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 5 19 64
Application for plugging filed April 5 (verbal) 19 64
Application for plugging approved April 5 (verbal) 19 64
Plugging commenced April 5 19 64
Plugging completed April 5 (7:00 P.M.) 19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3697 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	228 ft.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 540 feet
Set plug at 540 feet
20 sacks cement at 540 feet
Mud to 210 feet
Plug 1/2 sack hulls and 20 sacks cement
Mud to 35 feet. Wired plug
1/2 sack hulls and 10 sacks cement
Plugged rat hole with 2 sacks cement and 2 sacks hulls
Plugged with pump truck

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1964
04-08-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Route #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. Marvin Douglass (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. Marvin Douglass
6810 West Highway 45.54 Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April 19 64

My commission expires January 24, 1968

Allen P. Denton
Notary Public.

WELL LOG

15-051-01525-00-00

COMPANY Clinton Oil Company

SEC. 19 T. 13S R. 17W

FARM Madden

NO. 2

LOC. NW NE SW


TOTAL DEPTH 3700'

COUNTY Ellis

COMM. 3-28-64

COMP. 4-5-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 227' w/150 sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

75' Surface Clay
 227' Blue Shale
 775' Shale
 1015' Dakota Sand
 1175' Shale
 1338' Red Bed
 1383' Anhydrite
 1985' Shale and Shells
 2360' Lime and Shale
 2610' Lime
 2730' Shale and Lime
 2870' Lime
 3180' Lime and Shale
 3700' Lime
 3700' RTD

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1964
05-12-1964
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Madden #2 well.

Subscribed and sworn to before me this 17th day of April 19 64

My Commission Expires: September 23rd, 1967

Howard C. Fisher
NOTARY PUBLIC