

15-051-19357-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 19 Twp. 13 Rge. 17 (E) (W)<sup>A</sup>  
Location as "NE/CNW/SW" or footage from lines SE/SW/SW  
Lease Owner Clinton Oil Company  
Lease Name Madden "A" Well No. 1  
Office Address Box 404 Plainville, Kansas 67663  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed August 29 19 63  
Application for plugging filed December 18 19 72  
Application for plugging approved December 19 19 72  
Plugging commenced January 20, 19 73  
Plugging completed February 5, 19 73  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production December 15 19 72  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Lansing-Kansas City Depth to top 3443 Bottom 3468 Total Depth of Well 3673 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	188	None
				5 1/2	3672	1,931.91'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured T. D. Pushed a plug to 3400'. Dumped 20 ft. of sand and 5 sacks cement. Work pipe 3" to 7" on 2500 psi. Shot casing at 3010. Spotted 60 bbls. oil. Shot casing at 2800, 2400, 2100, 2000, 1920 feet. Pulled 37 joints yellowrap and 23 joints plain 5 1/2" casing. Squeezed well with 5 sacks hulls, 30 sacks gel and 120 sacks 50/50 Poxmix with 6% added gel.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
02-14-1973

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rockhold Engineering, Inc.  
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
Box 698 Great Bend, Ks. 67530 James W. Rockhold  
(Address)

Subscribed and sworn to before me this 8th day of February, 1973

My commission expires September 30, 1975  
Cathy Miller Notary Public.

15-051-19357-00-00

CLINTON OIL COMPANY  
 No. 1 MADDEN "A"  
 SE SW SW 19-13-17W  
 Ellis County, Kansas

ELEVATION: 2114 GL  
 2124 KB

Contractor: Raymond Oil Company, Inc. - Rig #9  
 Commenced: August 20, 1963  
 Completed: August 29, 1963 (Rotary)  
 Casing Record:  
 8-5/8" @188' w/140 Sx.  
 5-1/2" @3673' w/100 Sx.

Figures Indicate Bottom of Formation


<u>Formation</u>	<u>Depth</u>
Shale and Sand	715
Sand	1010
Shale and Shells	1354
Anhydrite	1400
Shale and Shells	1730
Redbed	1985
Lime and Shale w/Sand	2220
Lime and Shale	2485
Shale and Lime	2635
Lime and Shale	2815
Shale and Lime	2950
Lime and Shale	3290
Lime	3382
Lime and Shale	3455
Lime	3480
Lime and Shale	3520
Lime	3580
Lime and Shale	3690
Arbuckle	3720 RTD

Tops


Anhydrite	1352
Topeka	3110
Heebner	3370
Lansing	3418
Base Kansas City	3654 <i>4k</i>
Conglomerate	3670
Arbuckle	3688
Rotary Total Depth	3720

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I hereby certify the above to be true and correct to the best of my knowledge.

  
 Patrick R. Raymond, Exec. Vice President

Subscribed and sworn to before me this 4th day of September, 1963.

  
 Barbara A. Kennedy, Notary Public

My commission expires:  
 July 9, 1966