

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CE<sup>1</sup>/<sub>2</sub> NE NE

SEC. 19 TWP. 13 RGE. 16 W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Rome A

Operator G. M. R Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3514 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 163' circulated with cement.

Filled with rotary mud to 160', set wood plug 1/2 sack

Fiber seal and 15 sax cement, set wood plug at 100' with

1/2 sack fiber seal and 10 sax cement, filled with rotary mud

to 20', set wood plug 1/2 sack Fiberseal and filled hole to

bottom cellar with cement.

09-12-1950

**PLUGGING**  
FILE SEC 19 T 13 R 16W  
BOOK PAGE 27 LINE 18

[Signature]  
District Conservation Agent

Date 9-8-50

[Handwritten mark]