

15-051-19341-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas
05-25-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Jay Kornfeld

Complete Address 1313 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Rome Well No. 1

Location NW SE SW Sec. 19 Twp. 13 Rge. (E) (W) 16

County Ellis Total Depth 3521

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Gasing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 1P Day 19 Month 5 Year 1970

The above well was plugged as follows:

Total Depth 3521' 8 5/8 csg set at 200' cwc 165 sk.

5 1/2 csg set at 3515' cw 125 sk cmt.

5 1/2 csg Perf. (3250')

Set wood plug at 3250'. Sd (3235-3250) Dumped 5 sk cmt W/dump bailer. (3200-3235)

Cutoff and recovered 2740' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 130 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/25/70

INV. NO. 1946-W

Signed: Geo. F. Messing
Well Plugging Supervisor