

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: CS $\frac{1}{2}$ SE NW Sec. 19 Twp. 13 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3529

I have this date completed supervision of plugging of:

Lease Name: Geist Well No. 1

Operator's Full Name: K & E Drg Co

Complete Address: 719 Union Center Wichita, Kans

Plugging Contractor: Knight Casing Pulling Co

Address: Chase $\frac{1}{2}$ Kans License No. 436

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 8PM Day 15 Month 7 Year 60

The above well was plugged as follows:

8 5/8" 248' circulated with cement - 5 $\frac{1}{2}$ " at 3518' with 75 sax cement.
Filled with sand to 3500', set 4 sax cement with dump bailer, pulled 3000'
5 $\frac{1}{2}$ " to 500', circulated hole with heavy mud through 5 $\frac{1}{2}$ " at 500', displaced
20 sax cement through 5 $\frac{1}{2}$ " at 500', heavy mud to 160', displaced 20 sax
cement through 5 $\frac{1}{2}$ " at 160', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: *Edmond Pettig*
Conservation Division Agent

Reviewed: *J. Lewis Bush*
Field Supervisor

Remarks:

7/26/60
1690-W

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1960
CONSERVATION DIVISION
Wichita, Kansas