

15-051-02656-00-00

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1965  
02-23-1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Birmingham & Bartlett

Complete Address: 300 Kaufman Bldg Wichita, Kans

Lease Name Nowak Well No. 2

Location SE NW NE Sec. 36 Twp. 13 Rge. (E) (W) 16

County Ellis Total Depth 3384

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Ace Pipe Pulling Co & Sun Cementing Co

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 5:30PM Day 19 Month 2 Year 65

**The Above well was plugged as follows:**

8 5/8" 237' circulated with cement - 5 1/2" 3384' PB to 3377' Perf 3366'  
Filled with sand to 3350', set 4 sax cement with dump bailer - pulled  
2645' 5 1/2" to 450' - circulated hole with heavy gel mud through 5 1/2"  
at 450' ( 20 sax Gel) - displaced 20 sax cement through 5 1/2" at 450',  
heavy mud to 210', displaced 20 sax cement through 5 1/2" at 210', heavy  
mud to 35', cement 35' to 0'

Cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 2/24/65

INV. NO. 925-W

Signed: Edson Petty  
Well Plugging Supervisor