

15-051-20323-00-00

Form CP-3  
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11-04-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Schreiner Petroleum

Complete Address: 207 Petroleum Bldg., Wichita, Kansas

Lease Name Brungardt Well No. 1

Location NW SE NE Sec. 35 Twp. 13 Rge. 16 (E) (W) X

County Ellis Total Depth 3491

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Ralph Lynch Casing Pulling

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 3P Day 22 Month 10 Year 1968

The Above well was plugged as follows:

Total Depth 3491' 8 5/8 csg set at 250' cwc

4 1/2 csg set at 3490' cw 150 sc cmt.

Set wood plug at 3100', Poured 10 gal sand (3085-3100) dumped 4 sc cmt with dump bailer

(~~3015-3085~~)

Shutoff and recov. 2700' of 4 1/2 csg.

Pumped thru 8 5/8 plg container with 10 sc gel, plug and 130 sc 50-50 poz cmt W/6% gel.

Max. pres. 300 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. L. Massup  
Well Plugging Supervisor

DATE 11/4/68  
INV. NO. 8743-4