

11 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 1 1963
02-01-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt
Complete Address: Box 656 Hays, Kansas
Lease Name Brungardt Well No. 1
Location NW NW NE Sec. 35 Twp. 13 Rge. (E) (W) 16
County Ellis Total Depth 3473
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 5PM Day 30 Month 1 Year 63

The Above well was plugged as follows:

8 5/8" 175' circulated with cement - 5 1/2" 3471' with 125 sax cement - Perf 3418'
Filled with sand to 3400', set 4 sax cement with dump bailer - pulled 2807'
5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500' (30 sax Gel)
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 190', displaced 20
sax cement through 5 1/2" at 190', heavy mud to 35', set bridge and filled to
bottom cellar with cement.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/1/63
WELL NO. 6506-W

Signed: *Edon Kelly*
Well Plugging Supervisor