

15-051-20458-00-00

Form CP-3
Rev. 6-4-68

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1970
CONSERVATION DIVISION
Wichita, Kansas
04-13-1970

Operator's Full Name Clinton Oil Company
Complete Address 217 N. Water Wichita, Kansas 67202
Lease Name G. A. Kippes Well No. 1 - V
Location C S/2 NW SW Sec. 35 Twp. 13 Rge. (E) (W) 16
County Ellis Total Depth 3497
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Co.
Address Box 221 Great Bend, Kansas License No. 637
Operation Completed: Hour 3P Day 11 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3497' 8 5/8 csg set at 319' cwc
5 1/2 csg set at 3465' cw 125 sk cmt.
5 1/2 csg PBTB 3430' with perf. (3305-3138)
set wood plug at 3100' poured sand (3080-3100) dumped 5 sk cmt W/dump bailer. (3040-3080)
Cutoff and recovered 2742' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 130 sk 50-50
poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 4/13/70
INV. NO. 1709-W