

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,939-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Kennedy & Mitchell, Inc.

Complete Address P. O. Box 270, Lakewood, Colorado 80227

Lease Name Leng Well No. #45-714

Location SV NW NE Sec. 35 Twp. 13 Rge. 16 (East) ~~(West)~~

County Ellis Total Depth 3515'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc.

Address 251 N. Water, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 4:30PM Day: 14th Month: April Year: 19 82

Plugging Operations attended by Agent?: All XXX Part _____ None _____

The above well was plugged as follows:

8 5/8"-276' s.p. cuc. w/185 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks of cement

2nd plug @ 270' w/40 sacks of cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement.

Circulated 10 sacks of cement in rat hole.

Amount of Surface Casing: 276' of 8.5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1982
04-19-1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 4-28-82

INV. NO. 26-W

Signed: _____
Conservation Division Agent