

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 83-13  
~~XXXXXXXXXX~~  
LOCATION CR<sup>1</sup>/<sub>2</sub> SE SE  
SEC. 36 TWP. 12 RGE. 23

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease C.M. Monroe ANB KCC  
Operator Stanolind Oil & Gas Address Gorham, Kans  
Field \_\_\_\_\_ County Trego  
Total Depth 3974 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 202' circulated with cement.

5 1/2" at 3959' with 100 sax cement spotted behind - hole in  
pipe at 3466' - squeezed with 100 sax additional cement.

Pulled 2549' 5 1/2" - filled with mud to 200', set rock and  
15 sax cement, mud to 35', set rock and 10 sax cement to  
bottom cellar.

James J. Kelly  
District Conservation Agent

Date 3-26-53

MAR 30 1953  
03-30-53  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING** 22  
FILE SEC 36 T 12 R 23  
BOOK PAGE 83 LINE 13