

15-051-05535-00-00
R

ST. 11
AUG 5 1959
08-05-1959
DIVISION

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 52-22 County: Ellis
Location: SW NW SW Sec. 11 Twp. 13 Rge. 17 (E) (W)
Name of Field: _____ Total Depth: 3547

I have this date completed supervision of plugging of:

Lease Name: Dreiling Well No. 1

Operator's Full Name: Wilkinson Drg Co

Complete Address: 1121 Union Center Wichita, Kans

Plugging Contractor: R & D Casing Pulling

Address: Ellinwood, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 1 Month 8 Year 59

The above well was plugged as follows:

8 5/8" 201' circulated with cement - 5 1/2" 3532' with 100 sax cement
Filled with sand to 3520', set 4 sax cement with dump boiler, pulled
2750' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (30 sax
Gel), displaced 20 sax cement through 5 1/2" at 490', mud to 160', displaced
20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10
sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 12/21/59
INV. NO. 198-W