

15-051-01579-00-00

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-26-62

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

06-03-1968
2898

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Karlin Well No. 1

Location NE NW SE Sec. 11 Twp. 13 Rge. 17 (E) (W) X

County Ellis Total Depth 3550'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling

Address: 204 E. 6th Ellinwood, Kansas License No. 396

Operation Completed: Hour 4:30 P Day 29 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3550' 8 5/8 csg set at 160' cwc.

5 1/2 csg set at 3546' cw 125 sc cement.

5 1/2 csg PBTD 3540' with top perf at 3316'

Filled with sand to 3300' and dumped 5 sc cement with dump bailer.

Recov. 2898' of 5 1/2 csg.

Pumped thru 8 5/8 swage with 25 sc gel W/5 sc hulls and 130 sc 6% 50-50 poz cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Massey
Well Plugging Supervisor

DATE 6/4/68
INV. NO. 7851-4