

15-051-19356-00-00

Form CP-3  
Rev. 6-26-62

W KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1964  
01-07-1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty  
Complete Address: 800 Bitting Bldg Wichita, Kansas  
Lease Name Rome Well No. 1  
Location SE SW NE Sec. 11 Twp. 13 Rge. (E) (W) 17  
County Ellis Total Depth 3564  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Glenn & Smith  
Address: Ellinwood, Kans License No. 396  
Operation Completed: Hour 1PM Day 6 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 164' circulated with cement - 5 1/2" 3562' with 125 sax cement  
PB 3540' - perf 3339.

PB with plugs and sand to 3300', set 4 sax cement with dump bailer,  
pulled 2910' 5 1/2" to 550', circulated hole with heavy gel mud through  
5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', heavy gel  
mud to 190', displaced 20 sax cement through 5 1/2" at 190', heavy gel  
mud to 35' cement to bottom cellar.

Mudding and cementing by Sun cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/8/64  
INV. NO. 8427-W