

15-051 20623-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1970
CONSERVATION DIVISION
Wichita, Kansas
05-14-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Russell, Kansas

Lease Name Kuhn Well No. 1

Location SE NE SE Sec. 12 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3580'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. _____

Operation Completed: Hour 9P Day 12 Month 5 Year 1970

The above well was plugged as follows:

RTD 3580' 8 5/8 csg set at 250' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 5/14/70

INV. NO. 1892-W