

15-051-01584-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
03-17-1972

Operator's Full Name Clinton Oil Company  
Complete Address 217 N. Water Wichita, Kansas 67202  
Lease Name Madden Well No. 1  
Location SW SE SW Sec. 19 Twp. 13 Rge. (E) (W) 17  
County Ellis Total Depth 3735'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Co. Tools  
Address        License No.         
Operation Completed: Hour 4:30 P Day 14 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3735' 8 5/8 csg set at 173' cwc:  
5 1/2 csg set at 3627' cw 100 sk cmt.  
5 1/2 csg DV tool set at 1286' cwc to surface.  
5 1/2 csg PBTB 3627' with perf. (3421-3446) No pipe recovered.  
Ran tubing to 3440' -pumped 55 sk gel & water W/800 lbs hulls -displaced 20 sk  
50-50 poz cmt W/4% added gel.  
Pulled tubing out of hole. -ran wire line to 500' (top of fluid)  
Set rock & sand bridge (475-500) filled with 50 sk 50-50 poz cmt W/4% added gel  
(475 to base of cellar)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Murray  
Well Plugging Supervisor

INVOICED

DATE 3-17-72

INV. NO. 5364-W