

15-051-01525-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1964
04-09-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clinton Oil Co
Complete Address: 6810 West Highway 54 Wichita, Kansas
Lease Name Madden Well No. 2X
Location NW NE SW Sec. 19 Twp. 13 Rge. (E) (W) 17
County Ellis Total Depth 3700
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Garvey Drg Co & Sun Cementing Co
Address: License No.
Operation Completed: Hour 7PM Day 5 Month 4 Year 64

The Above well was plugged as follows:

8 5/8" 228' circulated with cement.

Circulated hole with heavy mud, set plug at 540', displaced 20 sax cement
through drill pipe, heavy mud to 210', set plug and displaced 20 sax
cement through drill pipe, heavy mud to 35', set plug, hulls and filled
to bottom cellar with cement.

Cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/9/64
INV. NO. 8919-W