

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

051

API Number 15-~~015~~-22, 102-00-00

245 North Water  
Wichita, KS 67202

Operator's Full Name ERNST-STEINLE OPERATIONS

Complete Address 1025-MAIN ST. RUSSELL, KANS. 67662

Lease Name ST AAB Well No. #1

Location NW-SW-SW Sec. 19 Twp. 13<sup>S</sup> Rge. 17 (East) (West)

County ELLIS Total Depth 3720 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor EMPHASIS OIL OPERATIONS (BRUCE FICKLE)

Address BOX 506 RUSSELL, KANS. License No. \_\_\_\_\_

Operation Completed: Hour 1:00<sup>AM</sup> Day 22 Month Nov Year 1980

The above well was plugged as follows:

8 5/8" 257 FT SD. CUL w/ 165 ST 60/40 Pozmix-2% GEL.-2% CA-CL.

ORDERED 110 ST 50/50 Pozmix 6% GEL. + 8 5/8" PLUG. - ELV. 2133' KB

SPOTTED WITH DRILL STEM, WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG. @ 720 FT w/ 70 ST CMT.

2<sup>ND</sup> PLUG. @ 240 FT w/ 25 ST CMT.

3<sup>RD</sup> PLUG. -> SOLID BRIDGE @ 40 FT / 60 w/ 10 ST CMT.

5<sup>TH</sup> IN RAT HOLE.

CEMENTED BY SUN CMT.

NOV 25 1980  
WICHITA, KANSAS  
CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Conservation Division Agent

DATE 12-10-80

INV. NO. 3722-W