

15-051-19357-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1973
02-00-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Marena Madden "A" Well No. 1

Location SE SW SW Sec. 19 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering

Address Box 221 Great Bend, Kansas 67530 License No. 637

Operation Completed: Hour 3:30 P Day 5 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3720' 8 5/8 csg set at 188' cwc: 140 sk.

5 1/2 csg set at 3673' cw 100 sk cmt

5 1/2 csg PBSD 3643' with top perf. (3434')

Set 5 1/2 wood plug at 3400' -poured 10' sand -dumped 5 sk cmt W/dump bailer. (3350-3400)

Cutoff and recovered 1900' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls, -70 sk cmt -5 sk

gel & water -released 8 5/8 plug and pumped 50 sk cmt by Sun Cementing Co. SI pres. 300 lbs

I hereby certify that the above well was plugged as herein stated.

Signed: Rec F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/7/73
INV. NO. 6946-W