

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051--22,554-00400

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name A. W. Leikam Oil Operations

Complete Address 505 Riley St., Hays, Kansas 67601

Lease Name Leikam Well No. #1

Location S/2 NE NW Sec. 8 Twp. 13 Rge. 17 (East)(West)

County Ellis Total Depth 3650'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Ranger Drilling Company, Inc.

Address P. O. Box 856, Hays, Kansas 67601 License No. _____

Operation Completed: Hour: 6:30AM Day: 4th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-201' s.p. cuc. w/130 sacks 60/40 posmix-2% Gel.-2% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated with 10 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
DEC - 5 1981
12-07-1981
CONSERVATION DIVISION
WICHITA KANSAS

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

1-19-82
8925 W