

15-051-21054-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1975  
05-12-1975  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt

Complete Address Box 370, Hays, Kansas 67601

Lease Name Staab Well No. 3

Location NW SW SE Sec. 8 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3627'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 8<sup>30</sup>P Day 9 Month 5 Year 1975

The above well was plugged as follows:

RTD 3627' 8 5/8 csg set 123' cwc Cmt. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.  
Heavy mud to 125' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.  
        
        
        
      

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/13/75

INV. NO. 1323-W

Signed: Leo J. Massey  
Well Plugging Supervisor