

15-051-30265-00-00

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
MAY 12 1966  
05-12-1966

Operator's Full Name DON F. PRATT

Complete Address: BOX 370 HAYS, KANSAS

Lease Name STAAB Well No. 2

Location SW-SF-SF Sec. 8 Twp. 13 Rge. 17 (E) (W) X

County ELLIS Total Depth 3619

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Leo Drilling Dr. Co

Address: Victoria, Kansas License No.     

Operation Completed: Hour 5-A Day 11 Month 5 Year 1966

The Above well was plugged as follows:

Total Depth 3619 8 5/8 set at 118' cement. circ.

Gunned pits circulated hole with heavy mud, set cementing plug at 540 ft..

and displaced 20 sac cement thru drill pipe, heavy mud to 160 ft.. set

cementing plug and displaced 20 sac cement thru drill pipe, heavy mud to 40 ft..

set cementing plug, 1/2 sac hulls and 1 sac cement, cementing to base of cellar.

Cemented rat hole with 2 sac cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 5/12/66  
INV. NO. 3204-W