

15-051-30266-00-00

Form CP-3
Rev. 6-26-62

KANSAS

JP

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

10-31-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Inc.,
 Complete Address: 410 Fourth National Bk. Bldg., Wichita, Kansas
 Lease Name Polifka Well No. 1
 Location C S/2 N/2 N/2 Sec. 8 Twp. 13 Rge. 17 (E) (W) X
 County Ellis Total Depth 3608
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Bert Self Casing Pulling Co.
 Address: R R # 4 Hutchinson, Kansas License No. 48
 Operation Completed: Hour 12 P Day 28 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3608' 8 5/8 csg set at 190' cwc. 135 sc.
 5 1/2 csg set at 3595' cw 125 sc cement.
 Sand back to 3565'- Dumped 5 sc cement with dump bailer.
 Recov. 2780' of 5 1/2 csg.
 Squeezed thru 8 5/8 plug container with 25 sc gel mud and 85 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo. Massey*
Well Plugging Supervisor

INVOICED

DATE 10/31/66
INV. NO. 4202-U