

15-025-20521-0000

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20521 ✓ f

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Chinook Energy Corp.

Complete Address 1716 Lynola St. 420 Denver Colo 80203

Lease Name Mr. Mininny Well No. 1

Location 2310' FSL-1810' FEL Sec. 2 Twp. 34S Rge. 22W (East)(West)

County Clark Total Depth 5510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling Inc.

Address 210 Rockborough Bldg 260 N Rock Rd. Wichita, Kans 67206 License No. _____

Operation Completed: Hour: 11:00 A.M. Day: 19 Month: November Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

^{85'}
There is 620' surface casing cement circulated. All fresh water is behind the surface casing. 1st plug at 1000' with 50 sks of cement pumped down with hole full of heavy mud. 2nd plug pushed rubber plug to 600' and pumped 35 sks on top of it. 3rd plug 40' to 0' with 10 sks of cement on solid bridge. They also pumped 5 sks of cement in each of the rat hole & mouse hole. The pusher for Eagle Drilling was Butch Steinent. Cement used was common with 3% oil & 2% c.c. Plugging accomplished by Halliburton Co. Libran out of Pratt Kans

I hereby certify that the above instructions were given as herein stated.

12-9-81
8587-W

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1981
11-24-81
CONSERVATION DIVISION
Wichita, Kansas

Paul Luttis
Conservation Division Agent