

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

OCT 23 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Graham-Michaelis Corp.

Complete Address Box 247, Wichita, Kansas 67201

Lease Name McMinimy Well No. 1-2

Location SE Corner Sec. 2 Twp. 34 Rge. 22 ~~(E)~~ (W)

County Clark Total Depth 5479'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lillard Casing Pulling

Address Woodard, Oklahoma License No. 618

Operation Completed: Hour 10:00AM Day 17 Month 10 Year 1973

The above well was plugged as follows:

8 5/8" to 582' circulated w/ cement. 4 1/2" to 5478' cemented.

Top perforations 5364' Plug bottom w/ 20 sacks cement.

Top of cement 5000' Mud 5000' to 580'

Spotted 35 sacks cement 580' to 480' Mud 480' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 4600' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

DATE 10/23/73

INV. NO. 8054-W

Signed: Edward J. Lued
Well Plugging Supervisor