

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1978
07-10-1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051 -21,509-00-00 (of this well)

Operator's Full Name Pate-Dombaugh Pet. & Martin Expl.
Complete Address 502 Union Center, Wichita, Ks.
Lease Name Kuhn Well No. 1
Location SW SW NW Sec. 24 Twp. 13 Rge. (E) (W) 17
County Ellis Total Depth 3570'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor B & B Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 5 P Day 7 Month 7 Year 1978

The above well was plugged as follows:
RTD 3570' 8 5/8 csg set 209' cwc 150 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rea Massey
Well Plugging Supervisor

DATE 7-11-78
INV. NO. 7626-W