

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW SW NW

SEC. 25 TWP. 13 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Braun P.O. Box 387 - Hoisington

Operator Woodman & Iannitti Address 717 Union Natl Wichita, Kans

Field _____ County Ellis

Total Depth 3584 Feet.

Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 164' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

500', displaced 20 sax cement through drill pipe, heavy mud to

155', set cementing plug, 1/2 sack hulls and 15 sax cement, heavy mud

to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom

cellar.

Gilbert Leiker

By *G. Leiker*

District Conservation Agent

Date 12-22-57

PLUGGING
FILE SEC 25 T 13 R 17
BOOK PAGE 72 LINE 1

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1957
12-24-1957
CONSERVATION DIVISION
WICHITA, KANSAS