

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-23,012-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Chief Drilling Company, Inc.

Complete Address P. O. 905, Century Plaza, Wichita, Kansas 67202

Lease Name Roth "B" Well No. 2529

Location SE NE NE Sec. 36 Twp. 13 Rge. 17 (East) (West)

County Ellis Total Depth 3539'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Warrior Drilling, Inc.

Address P. O. Box 905, Century Plaza, Wichita, Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 6:15AM Day: 17th Month: May Year: 19 82

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-200' s.p. cuc. w/140 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 200' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1982  
05-24-1982  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Signed: \_\_\_\_\_  
Conservation Division Agent

DATE 6-3-82  
INVOICE NO. 330-W