

15-051-00588-00-00



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 36 TWP. 13 RGE. 17

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Margaret Kuhn DNB rec

Operator Tennessee Gas Transmission Co Address Box 513 Chase, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3595 Feet.

Plugging Contractor Strata Drg Co & Globe Cementing Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_  
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

550', displaced 20 sax cement through drill pipe, heavy mud to

190', set cementing plug and displaced 20 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10

sax cement to bottom cellar.

Cementing by Globe Cementing Co.

District Conservation Agent

Date 9-14-57

09-23-1957  
RECEIVED  
DISTRICT CONSERVATION AGENT'S OFFICE  
WICHITA, KANSAS

PLUGGING  
FILE SEC. 36 T. 13 R. 17 W  
BOOK PAGE 47 LINE 44