

15-051-05542-00-00

*ye*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

11-28-1961

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: SE SW NE Sec. 23 Twp. 13 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 17  
Name of Field: \_\_\_\_\_ Total Depth: 3584

I have this date completed supervision of plugging of:

Lease Name: Dinkel Well No. 3

Operator's Full Name: Alpine Oil & Royalty

Complete Address: 800 Bitting Bldg Wichita, Kansas

Plugging Contractor Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 20 Month 11 Year 61

The above well was plugged as follows:

8 5/8" 150' circulated with cement. 5 1/2" 3576' with 150 sax cement.

PB 3520' perforated 3425'

Set plug at 3400', sand and 5 sax cement on top plug.

Bulled 2660' 5 1/2" to 500', circulated hole with heavy gel mud through 5 1/2"

at 500', displaced 20 sax cement through 5 1/2" at 500', heavy mud to 170',

displaced 20 sax cement through 5 1/2" at 170', heavy mud to 35', cement

35' to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edon Perry*  
Conservation Division Agent

Reviewed: *Harold Hollis*  
Field Supervisor

Remarks:

INVOICED  
DATE 12/5/61  
INV. NO. 4133-W