

15-051 - 00258 - 00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1963
04-30-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty
Complete Address: 800 Bitting Bldg Wichita, Kansas
Lease Name Dinkle Well No. 1
Location NE SW NE Sec. 23 Twp. 13 Rge. (E) (W) 1 7
County Ellis Total Depth 3561
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kans License No. 396
Operation Completed: Hour 8PM Day 26 Month 4 Year 63

The Above well was plugged as follows:
85/8" 202' circulated with cement - 5 1/2" 3558' with 125 sax cement -
PB 3517' - Perf 3336' - Set plug at 3300', sand and 5 sax cement set
with dump bailer - pulled 2800' 5 1/2" to 550', circulated hole with heavy
gel mud through 5 1/2" at 550' (20 sax Gel), displaced 20 sax cement through
5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2"
at 180', heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 4/30/63
INV. NO. 6948-1