

15-051-05541-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 1 1963  
05-01-1963  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty

Complete Address: ~~Dinkle~~ 800 Bitting Bldg Wichita, Kansas

Lease Name Dinkle Well No. 2

Location SW NW NE Sec. 23 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3549

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 1PM Day 29 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3531' with 150 sax cement

PB 3400' Perf 3335'.

Set plug 3300', sand and 5 sax cement set with dump bailer - pulled

650' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2"

(30 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud

to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',

cement 35' to 0'

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edon Lerdy*  
Well Plugging Supervisor

5/1/63  
6989-4