

15-051-02747-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

10-23-1961

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NW SW NW Sec. 23 Twp. 13 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 17

Name of Field: \_\_\_\_\_ Total Depth: 3496

I have this date completed supervision of plugging of:

Lease Name: Kuhn Well No. 6

Operator's Full Name: Alpine Oil & Royalty

Complete Address: 800 Bitting Bldg Wichita, Kansas

Plugging Contractor Glenn & Smith

Address: Ellinwood, Kans License No. 396

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 17 Month 10 Year 61

The above well was plugged as follows:

8 5/8" 153' circulated with cement - ~~2 1/2"~~ 4 1/2" 3490' with 150 sax cement

Perf 3310' - DV tool at 1170' circulated with mud to 0'

Set plug at 3280', sand and 3 sax cement set with dump bailer - pulled

2720' 4 1/2" to 500', circulated hole with heavy mud through 4 1/2" - displaced

20 sax cement through 4 1/2" at 500', heavy mud to 170', displaced 20 sax

cement through 4 1/2" at 170', heavy mud to 35', - cement 35' to 0'

Mudding and cementing by Sun Cementing Co.

Signed: Edon Petty  
Conservation Division Agent

Reviewed: Harold G. Heelis  
Field Supervisor

Remarks:

INVOICED  
DATE 10/30/61  
INV. NO. 3922-W