

15-051-19359-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
AUG 21 1973
08-21-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas 67202

Lease Name Rome "A" Well No. 11

Location SE SW SW Sec. 23 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3615'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2 P Day 17 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3615' 8 5/8 csg set at 167' cwc 165 sk.

5 1/2 csg set at 3613' cw 75 sk cmt.

5 1/2 csg PBD 3553' with top perf. (3329')

5 1/2 csg squeezed at 686' with 250 sk. No pipe recovered.

Dakato leak--set castiron plug at 3105'.

Pumped down 5 1/2 csg with 20 sk gel & water --released 5 1/2 plug and pumped 80 sk
cmt W/400 lbs hulls by Allied Cementing Co. Max PP 450 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/22/73
INV. NO. 7798-4

Signed: Leo F. Marney
Well Plugging Supervisor