



15-051-26623-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
05-14-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Oil has this

date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Russell, Kansas

Lease Name: Kuhn Well No. 1

Location: SE NE SE Sec. 12 Twp. 13 Rge. (E)(W) 17

County: Ellis Total Depth 3580 Oil Well

Gas Well  Input Well  SWD Well  D & AXX  Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent