



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1971

CONSERVATION DIVISION
Wichita, Kansas

02-24-1971

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Flake of Woodman - Iannitti has this
date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Par Oil Co.

Complete Address: 150 South 8th St. Salina, Ks.

Lease Name: Drees Well No. 1

Location: NE SW SE Sec. 19 Twp. 13 Rge. (E)(W) 17

County: Ellis Total Depth 3687' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red F. Massey
Conservation Division Agent