



15-051-22102-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bruce Fickle of Emphasis Oil operations has this date requested permission to plug the following described well:

Operator's Full Name: Ernst-Steinle Operations

Complete Address: 1025 Main St. - Russell, Kans. 67665

Lease Name: Staab Well No. II 1

Location: NW-SW-SW Sec. 19 Twp. 13^S Rge. 12^W (W)

County: Ellis Total Depth: 3730^{FT}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Fickle was instructed to plug the well as follows:

- 8 5/8" - 257^{FT} SP. CUC w/ 165ST 60/40 Pozmix - 2% Gel - 3% CAH.
- Ordered 110ST 50/50 Pozmix 6% Gel. + 8 5/8" Plug - ELV. 2123 KB
- Spot with Drill Stem - with Heavy mud Between all Plugs
- 1ST Plug @ 720 w/ 70ST Cmt.
- 2ND Plug @ 240 w/ 25ST Cmt
- 3RD Plug - Solid Bridge - Sullu Plug @ 40^{FT} 60 w/ 10ST Cmt
- 5TH In Cat Hole.

Very truly yours, (By Sam Cmt)

Marion Schmidt
Conservation Division Agent
11-25-1980