

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Aom of Pioneer Oils Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, Plainville, Mo. 67663

Lease Name: Comeau "B" Well No. 1 / 16

Location: SW SW NE Sec. 22 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3425'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Aom was instructed to plug the well as follows:

8 5/8" - 234' SP. cas. w/135 sacks common - 2% Gel. - 3% Cal. U.  
Ordered 140 sacks 5/8 permix - 4% Gel. 3% Cal. U. + 8 5/8" plug.  
Spot w/drill stem w/heavy mud between all plugs.  
1st plug @ 660' w/80 sacks - 2nd plug @ 250' w/40 sacks.  
3rd plug - solid bridge of balls + plug @ 40' w/10 sacks.  
Circulated 10 sacks in rat hole

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1982

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
Conservation Division Agent