



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 2-9-59, 19 , authorized the following plugging operation:

Operator's Full Name: Alpine Oil & Royalty

Complete Address: 800 Bitting Bldg Wichita, Kans

Lease Name: Kuhn Well No. 7

Location: NW SE NW Sec. 25 Twp. 13 Rge. 17 (E) (W)

County: Ellis Total Depth: 5000

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

8 5/8" at 150' circulated with cement - 4 1/2" 5000' with 150 sax cement
Perforated 5341'

Fill with sand to 5320', set 4 sax cement, pull 4 1/2" to 500', circulate
with heavy mud (Gel) through 4 1/2", displace 25 sax cement through
4 1/2" at 480', mud to 180', displace 20 sax cement through 4 1/2", mud
to 55', set bridge and 10 sax cement.

Very truly yours,

RECEIVED
 STATE CORPORATION COMMISSION

FEB 24 1959
 02-247959
 CONSERVATION DIVISION
 Wichita, Kansas

Signed:

Conservation Division Agent