



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilson of G&M has this

date requested permission to plug the following described well:

Mr. Wilson guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Corp

Complete Address: Box 247, Wichita, Kansas

Lease Name: McMinimy Well No. 1-2

Location: SE Corner Sec. 2 Twp. 34 Rge. 22 (E) (W)

County: Clark Total Depth 5479' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wilson was instructed to plug the well as follows:

8 5/8" to 582' circulated w/ cement. 4 1/2" to 5478' cemented.

Top perforations 5364' Plug bottom w/ 20 sacks cement.

Top of cement 5000' Mud 5000' to 580'

Spot 35 sacks cement 580' to 480' Mud 480' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,


Conservation Division Agent