


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 23 Twp. 13S Rge. 17WE (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name DINKEL Well No. 3  
Office Address 800 Bitting Building, Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed January 25, 1958 19  
Application for plugging filed November 6, 1961 19  
Application for plugging approved November 16, 1961 19  
Plugging commenced November 18, 1961 19  
Plugging completed November 20, 1961 19  
Reason for abandonment of well or producing formation non-productive

If a producing well is abandoned, date of last production November 3 19 61  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? ~~No~~ ~~Yes~~ yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Lansing-KC Depth to top 3267 Bottom 3499 Total Depth of Well 584 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	150'	Cemented
				5 1/2"	3576	2650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 3400 feet and ran 5 sacks of cement from 3400 to 3370 feet - pumped 9 sacks of mud at 500 feet and 20 sacks of cement; pumped 20 sacks of cement at 170feet and ran 10 sacks of cement to base of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1963  
07-12-1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company  
Address Box 114 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Bldg, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of November, 19 61

My commission expires August 10, 1965

Leigh Ann Murrell  
Notary Public.

15-051-05542-00-00

**WELL LOG**

ALPINE OIL & ROYALTY CO., INC.

Commenced: January 16, 1958

Contractor: Quaker Drilling Co., Inc.

Completed: January 25, 1958

Dinkel No. 3  
SE SW NE Sec. 23-13S-17W  
Ellis County, Kansas

Elevation: 1992 KB

**Casing Record:**

Set 8 5/8 inch casing at 150 feet with 150 sacks pozmix  
Set 5 1/2 inch casing at 3576 feet with 150 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Shale and Shells	290	Anhydrite	1165 / 827
Sand and Shale	435	Heebner	3221 -1229
Shale and Shells	555	Lansing	3267 -1275
Sand	630	Base of Kansas City	3499 -1507
Shale and Shells	830	Conglomerate	3508 -1516
Shale	950	Arkuckle	3572 -1580
Red Bed	1165	Rotary Total Depth	3580 -1588
Anhydrite	1210		
Red Bed	1490		
Shale	2035		
Sandy Lime and Shale	2170		
Lime and Shale	2422		
Shale and Lime	2550		
Shale	2810		
Shale and Lime	3065		
Lime and Shale	3165		
Shale and Hard Lime	3295		
Lime	3310		
Lime and Shale	3355		
Lime	3375		
Lime and Shale	3440		
Lime	3460		
Lime and Shale	3525		
Shale, Chert & Dolomite	3580		

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 12 1963  
07-12-1963  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SW NE of Section 23, Township 13 South, Range 17 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By: *Thomas M. McCaul*  
Thomas M. McCaul

SUBSCRIBED AND SWORN TO before me a Notary Public in and for Sedgwick County, Kansas this 28th day of January, 1958.

*Virginia Mandell*  
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1961