


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

County. Sec. 23 Twp. 13S Rge. 17W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE SW NE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name J. Dinkel Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed April 19, 1953 19__
Application for plugging filed April 23, 1963 19__
Application for plugging approved April 24, 1963 19__
Plugging commenced April 25, 1963 19__
Plugging completed April 26, 1963 19__
Reason for abandonment of well or producing formation non productive in commercial quantities
If a producing well is abandoned, date of last production April 23 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing, KC Depth to top 3272 Bottom _____ Total Depth of Well 3500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 202' | Cemented |
| | | | | 5 1/2" | 3558' | 2819' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3300 feet and ran 5 sacks of cement from 3300 feet to 3270 feet. Pulled 5 1/2" to 500' and pumped 19 sacks of gel mud and 20 sacks of cement, Pulled pipe to 200' and pumped 20 sacks of cement, Pulled pipe to 30 feet and pumped 10 sacks of cement from 30 feet to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1963
05-03-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 63

My commission expires August 10, 1965

Virginia A. Randall
Notary Public.

15-051-00258-00-00

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 4-7-53

Contractor: Quaker Drilling Co., Inc.

Completed: 4-19-53

J. Dinkel No. 1
NE SW NE Sec. 23-13S-17W
Ellis County, Kansas

Elevation: 1998 R.B.

Production:

Casing Record:

Set 202' of 8 5/8" with 125 sacks
Set 3558' of 5 1/2" with 125 sacks

(Figures Indicate Bottom of Formations)

| <u>FORMATION</u> | <u>DEPTH</u> | <u>FORMATION TOPS</u> | |
|-----------------------------|--------------|-----------------------|------------|
| Surface soil & Yellow Shale | 120 | Anhydrite | 1175 + 823 |
| Blue Shale & Lime Shells | 198 | Heebner | 3225 -1227 |
| Shale | 290 | Lansing | 3272 -1274 |
| Sand | 380 | Conglomerate | 3521 -1523 |
| Shale | 560 | | |
| Sand | 600 | | |
| Shale | 665 | T.D. (R) | 3561 |
| Sand | 800 | | |
| Red Bed and Shale | 1080 | | |
| Shale and Shells | 1175 | | |
| Anhydrite | 1205 | | |
| Shale and Shells | 1800 | | |
| Lime and Shale | 1850 | | |
| Shale and Shells | 1990 | | |
| Lime and Shale | 2185 | | |
| Lime | 2275 | | |
| Shale | 2435 | | |
| Lime and Shale | 2608 | | |
| Shale | 2790 | | |
| Lime and Shale | 3070 | | |
| Lime | 3135 | | |
| Lime and Shale | 3190 | | |
| Lime | 3336 | | |
| Lime and Shale | 3357 | | |
| Lime | 3440 | | |
| Shale and Chert | 3561 | | |

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1963
04-24-1963
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled NE SW NE of Section 23, Township 13 South, Range 17 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By: *James H. McCall*

Subscribed and sworn to before me this 20th day of April, 1953.

Vashti Bell

My commission expires:
Sept. 14, 1953